Item No.	Description of work	Unit	Rate	Quantity	Cost
			Rs. a. p.		
	III. *Metalling the Road.*				
1	Collecting and stacking boulders 2″ size for soling ..	C.yd.	1 0 0	65	
2	Consolidation of soling metal	,,	0 6 0	65	
3	Collecting, breaking, carting and stacking burnt metal 1½″ size with a lead of 3 furlongs ..	,,	3 4 0	74	
4	Spreading and consolidating of metal	,,	0 6 0	74	
5	Collecting spreading and consolidating gravel ..	,,	0 9 0	25	
6	Collecting and spreading sand	,,	0 10 6	6	
	Alternative items that may be found necessary consistent with changes that may be made during execution.				
1	Benching in hard rock for seating of foundations— 3″ to 6″ deep—				
	3″ deep	S.ft.	0 4 0	..	
	4½″ deep	,,	0 6 0	..	
	6″ deep	,,	0 8 0	..	
2	Exacavating in stoney soil and soft rock	C.yd.	0 6 0	..	
3	Size stone in surki cement combination mortar (1 : 8) proportion with bond stones 6′ apart in every course	C.ft.	0 8 0	..	
4	Constructing burnt brick in lime mortar parapet walls 1½′ thick and 2′ high of approved design with ornamental plasters at ends, including plastering, white-washing, etc., complete	R.ft.	1 4 0	..	
5	Constructing size stone in lime mortar pedestals of approved design 2′×2′×2½′ at ends, with coping slabs on top (1½′×1½′×6″)	No.	6 0 0	..	
6	Burnt stone slabs 6″ thick neatly dressed and fixed in pedestals vertically	S.ft.	0 10 0	..	

M. A. RAMANUJAM,
Executive Engineer.

CHITALDRUG DIVISION.

Notification dated 25th March 1940.

1. Sealed tenders will be received at the Office of the Executive Engineer, Chitaldrug Division, up to 3 P.M. on 10th April 1940, for constructing a bridge across left Waste Weir Valley of Dharampur Tank, Hiriyur Taluk.

2. Tenders in the prescribed form obtainable from the Office of the Executive Engineer, Chitaldrug Division, should be addressed to the Executive Engineer, Chitaldrug Division, in a sealed cover and superscribed as "Tender for constructing a bridge across left Waste Weir Valley of Dharampur Tank, Hiriyur Taluk." The name of the tenderer should also be superscribed on the top of the cover.

3. Each tender must be accompanied by a treasury challan for having credited to "17 (a) P.W. Deposits" a sum of Rs. 220 (Rupees two hundred and twenty only) in cash or Government Promissory Notes or Mysore Government Bonds, duly endorsed at face value or market value, whichever is less, as earnest money. The earnest money of the successful tenderer will be retained as security deposit for the due fulfilment of the contract. Such a deposit in cash will not carry any interest.

4. The tenders will be opened in the presence of such tenderers who wish to be present on 10th April 1940 at 3 P.M. The final acceptance of the tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender, or to assign any reason whatever for the rejection of any.

5. The name of the successful tenderer will be posted on the Notice Board in the Executive Engineer's office in due course. Within eight days of the acceptance of the tender, the successful tenderer will be required to execute an agreement in the departmental Schedule Contract Form for the due fulfilment of the contract, and for the execution of all items of work in accordance with the Bombay Specifications (1931).

6. Failure to comply with the condition 5 above or to agree to carry out the work in accordance with the specifications and agreements in force will entail forfeiture of the earnest money.

7. The earnest money of rejected tenders will be returned on submission of the receipt originally granted, along with an application to the Executive Engineer.

8. Copies of tender notification, contract documents, schedules and drawings may be seen at any time at the Executive Engineer's Office, Chitaldrug, on all working days, between 11 A.M. and 5 P.M. and the tender form be obtained from that officer on payment of four annas.

9. Specific rates should be given for each item in the schedule accompanying the tender and the rates should be in rupees, annas and pies and expressed in words and figures. Tenders offering a percentage reduction on the estimate amount will be rejected.

10. Any rates or lumsump amounts for the items not called for, if tendered by the tenderer, will not be taken notice of. The rates for such items may be entered in a separate schedule with date and reasons for the same.

11. No alterations which are made by the tenderers in the tender form in the nomenclature of the items of work will be recognised and if corrections are made, the tenders are liable to rejection.

12. There should be no alterations or erasures in the tenders in the rates of items and any corrections made in the rates should be attested to and the number of corrections, if any, in each page noted at the foot of the same by the tenderer.

13. No reference should be made to the Public Works Department schedule of rates.

14. In the event of the tender being submitted by a firm, it must be signed separately and severally by each member thereof or in the event of absence of any partner, it must be signed on his behalf by a person holding power-of-attorney authorising him to do so.

15. When once the rates tendered have been accepted, they will not be revised under any circumstances. In regard to items of work not tendered, the rates for the same will be calculated by the Executive Engineer on the basis of current rates for materials and labour with a contractor's profit of 5 per cent as may be approved by the Superintending Engineer. This shall be final and legally binding on the tenderer.

16. The quantities given in the schedule are only approximate and the drawings shown to the contractor are only tentative and are liable to alterations, omissions, deductions or additions, at the discretion of the Executive Engineer or his representative. The tendered rates will hold good for any quantity, whether higher or lower than those given in the enclosed schedule.

17. The work should be completed and handed over in a tidy condition to the Public Works Department by the end of 15th September 1940, failing which the Executive Engineer may, at his discretion, levy a penalty of Rs. per day, which will ordinarily be calculated at 12 per cent per annum on the total outlay as liquidated damages for non-fulfilment of contract, and will be recovered from the contractor's outstandings for the period exceeded by him beyond the time fixed and until the work is completed and handed over.

18. In all matters of disputes of any kind not specially provided for in the agreement or of rates, penalties, measurements, quality of work, etc., the decision of the Chief or the Superintending Engineer shall be final and legally binding.

19. No claim for damages for delays caused by officers of the department in the execution of the work will be considered, whatever may be the reasons for such delays. Contractors should bear this in mind when tendering for the work. Extension of time due to delays caused by the departmental officers will, however, be considered on the merits of each case.

20. The contract should not be sublet.

21. All materials, tools and plant and machinery that will be supplied by the Executive Engineer in the interest of the work shall be accepted by the tenderer at the rates fixed by the Executive Engineer. The tenderer will pay the hire on tools and plant and machinery as per rules from the date of taking over of such machinery, tools and plant from the Stores to the date of return thereto, the dates considered being the dates of acknowledgments of the vouchers in each transaction.

22. The contractor should arrange for the payment of royalty and tolls.

Note.—(*a*) The contractor should at his own cost—

(1) Provide rods, stakes, ropes and labour required in setting out the works.
(2) Provide all necessary scaffolding, centering labour and appliances for hoisting.
(3) Provide mortar mills and sheds, to keep materials under cover and also for workmen.
(4) Arrange for protecting work during inclement weather.
(5) Supply requisite temporary lights, water cisterns, water pumps and hoses, sieves, parahs, shoring, strutting and other requisite protective appliances during the progress of the work.
(6) Supply all water required for work and workmen and shall provide temporary latrines and drains.
(7) Clean away all dirt, rubbish, superfluous materials and debris as they accumulate.
(8) Provide arrangements for pumping and baling of water from excavations and foundations, wherever and whenever necessary with his own pumping apparatus including necessary leading drains, slump pits, etc.
(9) Afford facilities to any other parties employed upon the work by the P. W. D. so that their work may proceed during the progress of the contract, and give such persons the use of ordinary scaffolding and ladders.

(10) The contractor is responsible for all accidents to workmen, etc., on the work, and he must take precaution against all risk of accidents and, if necessary, provide for the same by insurance at the proper time.

Note.—(*b*) It is the business of the contractor to make his own arrangements for quarries and supplies of materials.

23. Chamundi Brand Cement should to be used.

24. Items of work not included in the estimate will be paid for at lowest Schedule of rates.

Abstract Estimate for constructing a bridge across left waste weir valley of Dharmapur Tank, Hiriyur Taluk.

Sl. No.	Items of work	Unit	Quantity	Rate	Tender rates in	
					Figures	Words
				Rs. a. p.		
1	Earthwork excavating foundation in rocky strata and using the same for approach bank :—					
	(*a*) In soft rock	C.yd.	54	0 8 0		
	(*b*) In hard rock	,,	27	1 8 0		
2	Laying burnt stone jelly concrete in surki mortar combined with cement (1 : 10 for the levelling course) and tamping	C.ft.	912	0 6 0		
3	Burnt stone masonry in composite mortar with bonds at every 6′ apart	,,	2,154	0 6 0		
4	Burnt size stone masonry in lime mortar	,,	1,586	0 4 6		
5	Dressing the edges of corner stones and cut waters :—(as per execution)	L. S.		50 0 0		
6	R.C.C. 1 : 2 : 4 decking slab complete (cast in site and cured) with necessary reinforcements including centering charges, etc.	C.ft.	800	1 12 0		
7	Wearing coat of cement concrete 1 : 2 : 4, 2″ thick	,,	178	0 12 0		
8	1 : 3 Cement mortar pointing the masonry racking all joints and cutting lines	Sqr.	25·57	4 0 0		
7	Providing and fixing two rows of galvanized pipe 1½″ dr., hand railing with angle iron supports at every 5′ apart	R.ft.	212	1 12 0		
10	Bailing out water including connected works like sand bags, coffer dams, etc., (as per execution)	L. S.		300 0 0		
11	Unforeseen items of work	,,		132 0 0	(as per execution)	

B. TIRUMALACHAR,
Executive Engineer.

MEDICAL DEPARTMENT.

OFFICE OF THE SECRETARY, VICTORIA HOSPITAL, BANGALORE.

Notification dated 28th March 1940.

It is hereby notified for the information of the general public that the following unserviceable articles of the Victoria Hospital, Bangalore, will be sold by public auction on Wednesday the 10th April 1940, in the premises of the Victoria Hospital, Bangalore City. The articles will be knocked down to the highest bidder who should immediately pay the bid amount on the spot and arrange to remove the articles, failing which the articles will be resold at his risk.

The undersigned reserves to himself either to accept or reject any bid at his discretion and his orders will be final in the matter.

LIST OF ARTICLES.

1. Furniture, etc.—

1.	Milk crates	14	
2.	Meat safe	1	
3.	Indian commodes with pans	3	
4.	Table without drawers	1	
5.	Unit cot	1	
6.	Old rugs (coir)	5	
7.	Towel racks brass	2	
8.	Teak wood bread tray	1	
9.	Hip bath tub	1	
10.	Fly traps	2	
11.	Semi circular tables	1	